

PART LIST				
ITEM	QTY	PART NUMBER	WEIGHT	
1	1	2100mm Pole Base	1,840 kg.	
2	2	5 x 110 Lifting Insert		


OF	OPTION'S			
BOLT SPACING (mm)	GALVANIZED ANCHOR BOLT			
150	19 x 610mm			
160	19 x 610 mm			
180	25 x 920 mm			
197	25 x 920 mm			

Notes:

- 1. 2100mm Precast Parking Lot Pole Base to be built as shown.
- 2. Unit supplied with required anchor bolts, spacing PVC conduits as required.
- 3. Unit c/w lifting inserts as required.4. Unit Supplied with Nuts and Washers as required.
- 5. Minimum concrete strength: 30 MPa.
- 6. Welded wire mesh min. yield strength: 448 MPa.
- 7. Minimum rebar yield strength: 414 MPa (Steel Grade: G30.18 - 400 weldable)
- 8. All dimensions are in millimeters.
- 9. Installation & backfilling is the responsibility of others.
- 10.V- Groove Drain Trough to Start at Zero Depth in Centre of Base to 10mm at the Outside edge. Align with Conduit.







Elevation View

Note: 25mm Spacing

between Conduits

Langley Concrete Group is a certified Q-Cast Plant, an American Concrete Pipe Association Third Party Certification for the manufacture of Pipe, Manhole, Box Culvert & Precast Items.



Quality Assurance of products manufactured by The Langley Concrete Group has been verified by the following third party certification programs





All Dimensions are in Millimeters. Unless otherwise Stated

Projection Method: THIRD ANGLE



The LANGLEY CONCRETE Group of Companies

www.langleyconcretegroup.com LANGLEY (604) 533-1656 VICTORIA (250) 478-9581 CHILLIWACK 1-800 667-9600

This drawing is the property of the angley Concrete Group of Companies. All information contained herein

is confidential and may not be used in whole or in part without written permission from the owner

DESCRIPTION:

Precast Concrete Pole Base 2100 mm Parking Lot Pole **NON-MMCD**

DRAWN BY: BY	JOB NO.
CHK BY: KS	DWG NO: LPB-2100-NON-MMCD
DATE: Jan.03, 2020	LC NO:
SCALE: 1:18	MU NO:
SIZE REV. 11 x 17	SHEET 1 OF 1